

03/17/00  
JC780 U.S. PTO

3-20-00  
**FISH & RICHARDSON P.C.**

*A*  
4350 La Jolla Village Drive  
Suite 500  
San Diego, California 92122

Telephone  
858 678-5070

Facsimile  
858 678-5099

Web Site  
www.fr.com

Frederick P. Fish  
1855-1930

W.K. Richardson  
1859-1951

March 17, 2000

Attorney Docket No.: 06618/120002/CIT2580-D1

**Box Patent Application**

Assistant Commissioner for Patents  
Washington, DC 20231

Presented for filing is a new divisional patent application of:

Applicant: RODNEY M. GOODMAN, KAREN EMERSON AND JEFFREY  
DICKSON

Title: TELEVISION ADVERTISING AUTOMATED BILLING SYSTEM

The prior application is assigned of record to California Institute of Technology,  
a California corporation, by virtue of an assignment submitted to the Patent and  
Trademark Office for recording on June 12, 1998 at 9250/0073.

Enclosed are the following papers, including those required to receive a filing date  
under 37 CFR 1.53(b):

	<u>Pages</u>
Specification	35
Claims	1
Abstract	1
Declaration	3
Drawing(s)	12

Small entity status established in a parent case is still proper and desired.

Enclosures:

CERTIFICATE OF MAILING BY EXPRESS MAIL

Express Mail Label No. EL584779215US

I hereby certify that this correspondence is being deposited with the  
United States Postal Service as Express Mail Post Office to Addressee  
with sufficient postage on the date indicated below and is addressed to  
the Assistant Commissioner for Patents, Washington, D C. 20231

Date of Deposit

March 17, 2000

Signature

*Rich Donovan*

Typed or Printed Name of Person Signing Certificate

**FR**

BOSTON

DELAWARE

NEW YORK

SAN DIEGO

SILICON VALLEY

TWIN CITIES

WASHINGTON, DC

JC600 U.S. PTO  
09/528479

03/17/00

Assistant Commissioner for Patents

March 17, 2000

Page 2

- Form PTO-1449, 1 pages, listing documents cited in the parent application(s). Please confirm that these have been considered in this application by returning a copy of the Form PTO-1449 with the examiner's initials.
- Preliminary amendment, 2 pages.
- Postcard.

There are 3 total claims, 1 of which is independent.

This application is a divisional (and claims the benefit of priority under 35 USC 120) of U.S. application serial no. 08/979,838, filed November 26, 1997. The disclosure of the prior application is considered part of (and is incorporated by reference in) the disclosure of this application.

Basic filing fee	\$345
Total claims in excess of 20 times \$9	\$0
Independent claims in excess of 3 times \$39	\$0
Fee for multiple dependent claims	\$0
Total filing fee:	\$345

A check for the filing fee is enclosed. Please apply any other required fees or any credits to deposit account 06-1050, referencing the attorney docket number shown above.

If this application is found to be incomplete, or if a telephone conference would otherwise be helpful, please call the undersigned at (858) 678-5070.

Kindly acknowledge receipt of this application by returning the enclosed postcard.

Please send all correspondence to:

SCOTT C. HARRIS


Customer Number: 20985

Fish & Richardson P.C.

4350 La Jolla Village Drive, Suite 500

San Diego, CA 92122

Respectfully submitted,

  
Scott C. Harris

Reg. No. 32,030

Enclosures

SCH/rpi

10023403 doc

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

Applicant : Goodman, et al.      Art Unit: Unknown  
Serial No.: to be assigned      Examiner: Unknown  
Filed : March 17, 2000  
Title : TELEVISION ADVERTISING AUTOMATED BILLING SYSTEM

Assistant Commissioner for Patents  
Washington, D.C. 20231

PRELIMINARY AMENDMENT

Sir:

Prior to the examination of the above-referenced case,  
kindly amend the application as follows:

In the Specification:

Page 2, line 7; please delete "are" and substitute therefor  
--is--.

Page 4, line 3; please delete "understandably".

Line 8; please delete "a" and substitute therefor --  
an--.

Page 5, line 12, after "of", insert -commercial airing--;

CERTIFICATE OF MAILING BY EXPRESS MAIL

Express Mail Label No. EL584779215US

I hereby certify that this correspondence is  
being deposited with the United States Postal  
Service as Express Mail Post Office to Addressee  
with sufficient postage on the date indicated  
below and is addressed to the Assistant  
Commissioner for Patents, Washington,  
D.C. 20231.

Date of Deposit March 17, 2000  
Signature Rich Donovan  
Typed or Printed Name of Person Signing  
Certificate

line 15; please delete "comparisons" and substitute therefor --comparison--.

Page 6, line 9; please delete "problems" and substitute therefor --problem--.

Page 9, line 7; before "are" please insert --that--.

Page 11, line 22; please correct the spelling of "indicative".

Page 12, line 14; please delete "taken" and substitute therefor --taking--.

Page 16, line 4; before "that" please insert --is--.

Page 25, line 25; before "video" (first occurrence), please insert --to--.


Page 28, line 6; before "which" please insert --in--.

Page 34, line 23; after "to" please insert --be--.

Please apply any charges or credits to Deposit Account No. 06-1050.

Respectfully submitted,

Date: 3/17/00

  
\_\_\_\_\_  
Scott C. Harris  
Reg. No. 32,030

Fish & Richardson P.C.  
Customer Number: 20985  
4350 La Jolla Village Drive, Suite 500  
San Diego, CA 92122  
(858) 678-5070 telephone  
(858) 678-5099 facsimile  
www.fr.com web site

10023411.doc

APPLICATION  
FOR  
UNITED STATES LETTERS PATENT

TITLE: TELEVISION ADVERTISING AUTOMATED BILLING  
SYSTEM


APPLICANT: RODNEY M. GOODMAN, KAREN EMERSON AND  
JEFFREY DICKSON

CERTIFICATE OF MAILING BY EXPRESS MAIL

Express Mail Label No. EL584779215US

I hereby certify that this correspondence is being deposited with the United States Postal Service as Express Mail Post Office to Addressee with sufficient postage on the date indicated below and is addressed to the Assistant Commissioner for Patents, Washington, D.C. 20231.

Date of Deposit March 17, 2000

Signature 

Typed or Printed Name of Person Signing Certificate Rich Donovan

004482340

TELEVISION ADVERTISING AUTOMATED BILLING SYSTEM

FIELD OF THE INVENTION

The present invention relates to a media advertising  
automatic billing system which automatically and securely  
maintains an exact tracking of advertisements which are played  
and produces billing information for those advertisements.

BACKGROUND OF THE INVENTION

Commercial advertising ("commercials") create the revenues  
that sustain the content provider's operation. Commercials -  
provide a host of special problems based on the nature of the  
media.

Specifically, media such as television and radio sell  
specific time slots for playing of the advertisement. The  
content provider, e.g., the television station, sells a time slot  
in which a commercial will be played.

This arrangement creates special considerations. The  
station is selling time. Once that time passes, the value of the  
service goes to zero. Similarly, after the commercial plays,  
there is no way of unplaying it. This compares with other  
sellers of commodities, who often have the option to repossess  
the chattel being sold.

Because of these considerations, most stations require that  
payment for booking be entirely in advance, except for the best,

i.e, the most creditworthy accounts.

The most typical advertisement includes regular television commercials, typically thirty to sixty seconds in length, which are aired during breaks in commercial television programs. The so-called infomercial is also a television commercial advertising, but are typically much longer in length, e.g. between four minutes and one hour.

With the exception of certain public service-oriented advertising, all commercials are paid for by a sponsor. The billing is done on a per-piece basis, based on the time and - likely audience for the commercial. This pricing is a multi variable determination. For example, a one-minute commercial aired during the Super Bowl is considerably more expensive than a one-minute commercial aired at 2:00 A.M. Therefore, it is extremely important that the time when the commercial airs is the same time as what was paid for. However, it is not always a routine matter for the station to determine this.

A nationwide television commercial is often received by the television station, e.g., via its satellite transponder hook-up. A "nationwide" television commercial is often included as part of the nationwide program. In this case, the central network provider provides both the television program and some of the commercials to be aired everywhere. However, other breaks within the commercial television program may be filled by "local"

commercials, those that are aired only locally. These local commercials are typically produced locally, recorded and stored at the television station.

5            Nationwide programming time schedules for the affiliates are sent to local television affiliates from the network. This includes a schedule describing open times for local advertisement station identification and other time slots that the station can sell locally. Each half hour slot generally has two programming  
10 slots of 12 minutes duration with commercial slots in between. The national schedules also often leave half hour time slots open for infomercials or public access programming. Television guides often show these slots as "paid programming".

15            Depending on various circumstances, the local television station may have the option to override the national commercial. At times, the local station overrides the national commercial even when such an override is not authorized. This provides a significant problem of tracking which commercials have been shown and when.

20            The advertiser may pay in advance for a half hour to be aired at 7:30 P.M., but the commercial actually airs at 10:00 P.M. These times may have radically different prices. The price of a commercial aired at 9:02 P.M., which is after the show that aired in the 8:30 to 9 time slot can even be significantly  
25 different from the price of a commercial aired at 8:58 P.M.,



which is during that time slot. The advertisers are  
understandably, therefore, extremely interested in knowing the  
precise time of airing. However, the varied nature of the  
advertising system, and especially the television system often  
makes it difficult to determine precisely when the commercial  
will be aired.

Typically, the advertising agency acts as a intermediary  
between the actual advertisers and the television station. The  
advertiser wants their advertisement to air at certain times on  
certain channels and in certain events. For example, a toy -  
company might want their advertisement to air during the Sunday  
morning cartoons. Airing the advertisement during Sunday  
football would not reach the desired audience.

Special prices are often negotiated based on whether the  
advertisement is in prime time, off prime time, holidays,  
weekends, special events or the like.

At some time before the actual airing of the broadcast, the  
station produces an actual program schedule which show the  
programming segments it will play or receive, as well as all  
commercials, infomercials and station identifications. Each of  
the latter are stored on tape which are pulled from the video  
library by a station engineer. Commercials and infomercials are  
usually manually played by the station engineer who initiates the  
proper tape based on a schedule in a specified time slot. The

engineer keeps manual records of what has actually been done and the billing of commercial time is carried out based on these records.

5       The actually-played commercials are often sampled by third party organizations who employ people to watch and keep track of television commercials which are played. These people, however, cannot watch every single television commercial, and therefore only act as a sampling mechanism to determine a percentage of correct reporting by the television station and advertising agency.

10       One other means of verification of digitizes one or several frames of the commercial. Then the physical airing is taped and compared to the frames. This still requires a television to receive the broadcast and a physical comparisons of the frames. This method is inaccurate and again based on statistical sampling.

#### SUMMARY OF THE INVENTION

20       Recent studies have suggested that perhaps as many as fifty percent of the reported commercials are not played in their proper time. This is often because of the great demands that are placed on the station engineers. The station engineers are often simply too busy to keep accurate reports of the commercials in view of the many different demands that are placed on them.

25

Moreover, since the scheduling process is largely fluid in nature, the reports made by these engineers are crucial. The billing and accounting is done based on these reports, and their accuracy is, as described above, difficult to ascertain.

In addition, moreover, the manual billing system described above requires a crucial part of the billing to be manually entered. This system has never been satisfactorily automated.

Added to this is the problems obtained from the nature of the system in which the commercial can't be taken back once it has been played. Hence, the stations have no effective means of repossession.

The inventors of the present invention recognized all of these problems and realized that a real-time automated system for tracking the actual commercials that were aired would effectively be a win-win situation: for not only the advertisers who would get an exact accounting of when their commercial was aired, but also the television stations who would know exactly when the commercial was aired and would secure an automated means for determining the real percentage of scheduling anomalies.

The current system of payments for commercials by the advertiser usually requires payment prior to the airing of the commercial. In addition, the TV station is often required to sign an affidavit confirming the actual airing if so required by

the advertiser. An objective of the present system is to have a system that pays for the commercial on a "real-time" basis using an automated clearinghouse system. The objectives include:

- i. The TV Station gets a means to receive payment for their services - which is why advance payment is the standard norm of payment terms;
- ii. The advertising agency gets a means to receive payment for their services - a commission for the actual airing of time booked by the agency; and
- iii. The advertiser (Sponsor) gets a means to insure - airing of a commercial at the agreed-upon time and price.

Each entity wants accurate accounting of the commercial in addition to a more efficient, less cumbersome process of the payment transaction with reduced collection cost. This system describes a clearinghouse system to meet all of these objectives.

In view of the above, the inventors have provided a system which marks the commercials in a way that ensures secure and unambiguous identification of the subject matter. Each commercial is played by the television station including a secure identification. That identification is received, date and time confirmed, and verified. The information is sent to a billing computer.

The security is enhanced in this system. One embodiment uses a cryptographic system. Another uses a system which restricts access to the hardware.

5 A cryptographic system can be used to ensure that the information has not been tampered or faked. This provides the billing computer with a secure, computer-manipulable record indicating when the commercial was aired. The billing is done automatically by a computer program based on the data received  
10 from the actual airing of commercials.

15 The inventors also noticed a number of problems which could exist in such a system and have provided solutions to these problems also. One problem comes from the marking of commercials itself. Many have tried to analyze the content of commercials, so that such commercials could be automatically identified by an electronic circuit. Such an electronic circuit would then presumably either blank the commercials or turn off the video recording device so that the show could be watched in its entirety without commercials. Naturally, the advertisers are  
20 very hostile to the existence of such a system, since this would defeat the effect of their paid-for commercial time. A code on each commercial would be a sure way of detecting such a commercial. Therefore, the system preferably includes a way to avoid detection of the commercial. One way is by removal of the  
25 code prior to airing.

Another problem is the possibility of dishonest television stations or billers. A secure system requires that non authorized persons be prevented from tampering with the detection or improperly or falsely providing the detection. In view of the above, the inventors have devised embodiments which include special encryption techniques are used which make it difficult for an unauthorized party to properly code the commercial in a way that would fool the billing computer.

Another system correlates content of the commercial with the billing system to avoid the possibility of simply copying a code from one commercial on to another.

Another system adds some measure which prevents using this system to detect whether program content is a commercial.

The present system, titled the "ADTAG" system, uses a clearinghouse concept. Once the billing information is collected via the tracking system, a settlement between the advertiser, the advertising agency, and the TV or radio station is made via electronic means such as a modem or the Internet. This settlement is an accounting of the transaction and payment for the transaction between the three entities- again via electronic means.

The ADTAG clearinghouse system includes a verification portion which verifies in real time that a commercial has actually been aired, along with verification of the time when the

airing occurred. This information is used to authorize payment if all information matches or to initiate an error resolution procedure if the information does not match.

5

BRIEF DESCRIPTION OF THE DRAWINGS

All of these will be described in detail with reference to the accompanying drawings wherein

10 Fig. 1A shows a block diagram of the clearinghouse of the present invention;

Fig. 1B shows a basic block diagram of the overall system of the present invention;

Fig. 1C shows an alterative block diagram of a different embodiment;

15 Fig. 2 shows a tape tagger;

Fig. 3 shows a diagram of the teletext-text packet system;

Fig. 4 shows one possible encryption system for encoding;

Figs. 5A and 5B show the schematic of the preferred system of the present invention;

20 Fig. 6 shows an encoder flow diagram;

Fig. 7 shows a television monitor system block diagram;

Fig. 8 shows a decoder flow diagram; and

Fig. 9 shows a flowchart of the billing and verification done by the ADTAG system.

25

DESCRIPTION OF THE PREFERRED EMBODIMENTS

The present specification describes billing for an advertisement which is broadcast over a medium. The medium could be of any type. Television is described as the preferred embodiment of the medium.

Video sent over a channel is often transmitted using the teletext standard, which is a packet transmission method for transmitting video. The video is formed of a number of pixels arranged in lines. The lines are used to transmit the digital information.

Each line is transmitted from the left side of the screen to the right side of the screen. The cursor that writes the information thereafter needs to move from the right side of the screen back to the left side of the screen. The display is blanked during this time of retrace. This time is referred to as the vertical blanking interval or "VBI". Information can be stored in these times of retrace.

The NTSC video standard uses 525 lines with VBI lines in lines 6 through 21 and lines 258 through 273. Some of these lines are already in use for other functions. For example, VBI line 21 includes codes that are indicative of closed captions.

Fig. 3 shows the contents of the teletext packet. The control bytes 300 include header information that identifies the contents of the user data that includes the ADTAG packet. This



allows the system to mark the data as proprietary to avoid confusion of other teletext receivers by using a unique code.

The user bytes are encoded in order to ensure reliable transmission. The present system uses one or more VBIs per full frame of video. The raw data frame without forward error control includes 28 bytes per packet (8 bits per byte, sixty packets per second = 1340 bits per second) requiring a data transmission speed of 13.44 kbs.

A preferred forward error correction system includes the single error correcting double-error detecting Hamming code.--Many other codes could be used.

This allows a true reliable data rate of 6.72 kilobits per second. Therefore, for example, in the space of time taken up a 30 second television slot, approximately 200,000 bits of reliable information can be delivered. Standard DES with 64, 128, or 256 bit keys could be used. Preferably, the system also uses some correlation technique that correlates the code with the commercial in a way that prevents simply copying the code from one commercial to another.

The clearinghouse system is illustrated in Fig. 1A. To use the system, an advertiser 180 usually first obtains a line of credit for advertising from a financial institution 182. This

can be considered roughly analogous to a VISA card. The financial institution assigns an account number and credit limit. This account number will be used for charging later advertisements. The user then joins the ADTAG clearinghouse 186.

The ad agency 184 then books a commercial by obtaining the advertiser's account code along with other information about the advertisement. The booking information may include:

BOOKING INFORMATION

Agreed upon air date and time, duration of commercial  
Advertiser account code  
TV station account code  
Tape name and production date  
Ad agency account code  
Agreed upon pricing and commission

This information is usually obtained by the ad agency. However, larger advertisers can have their own in-house booking departments that could sign on to ADTAG directly. ADTAG then takes this information and develops reports for each entity based on the service agreement signed with ADTAG. Reports will be for that entity only - i.e., ad agency #1 can only get information related to ad agency #1 and not for any other entity. Reports can be generated including:

Conflicts in scheduled time  
Daily, weekly, monthly booking report for planning purposes  
TV stations booked  
Booking by advertiser.

The ad agency also joins the ADTAG clearinghouse system and agrees to abide by its program guidelines. The ad agency books a commercial or time slots with the ADTAG clearinghouse for its customer. The agency enters its account code, the customer accounts code, pricing for the commercial and the agency's commission code into the clearinghouse data base. At this point a reserve is entered onto the advertiser's credit line - similar to the way in which car rental firms and hotels put a reserve on a credit card when you rent a car or room. This reserve is removed by ADTAG when actual airing data is received or the air date time has expired.

ADTAG provides reports and information on a real time basis back to the ad agency, TV Station, and advertiser, based on the level of service selected by each entity.

When a commercial is played, ADTAG also decides if the commercial has been played at the precise same time as what was booked. If so, ADTAG "verifies" the playing, and "authorizes" payment from the bank. If not, the system initiates error resolution procedures.

An advertisement is made by digitally encoding certain information onto the tape which will be used to air the advertisement. Tape encoding will be provided by ADTAG or an ADTAG endorsed duplication house. The encoding is done on the master tape of the commercial production. In that way, any tape

5 duplicated off the master tape will include all the proper coding. In addition, ADTAG uses some kind of verification of security. This can be an encrypted code on the tape, and/or requiring secure premises and secure handling of the tape. The tape is then sent back to the advertiser (sponsor) or to whomever the sponsor authorizes. This is the first part of the security system. This information preferably includes, for example:

- the advertiser's ADTAG account code:
- The name of the tape
- Date the tape was produced
- Last date the tape should be used
- Certain copyright information
- Any other information about the tape which may be useful.

15 The information is preferably digitally encoded in some way associated with the advertisement that is actually playing during the advertisement.

20 The ADTAG code is included on the tape by a secure encoder. This can be done as follows:

a) The preferred technique uses ADTAG in a secure premises. The master tape is sent to ADTAG who adds the code. The master tape is returned including the duplicating code, and sent to the duplication house and then on to the TV stations. This allows keeping the encoder only at secured premises. Powerful

one-time-pad codes can be used in this case, e.g., where only the ADTAG computer knows the key.

A possible disadvantage that this system requires one extra recording and this may reduce the quality of the master. An all-digital system can be used to minimize any such degradation.

b) ADTAG-produced encoder boxes that are sent to any person who wishes to put ADTAG codes on a master tape. The encoders use an encryption scheme. This alleviates the problem of requiring an extra recording. But this has a possible problem that the encoder boxes could be subverted if the code is broken.

The preferred technique uses the digital encoding of the information into the vertical blanking intervals in a secure manner using a key encryption system. This system that is used needs to be secure and able to detect attempts to tamper with the code.

c) An alternate technique encodes information as part of the closed captioning part of the commercial. This can be readable information, e.g., the first line of text of closed captioning can be used to identify the commercial.

The security in this case comes from the literally thousands of people who will see the captions.

The tape is sent to the television station which sets it up for play matched to the station production schedule.

The station also may include an ADTAG decoder receiving the actual broadcast information. The ADTAG decoder recognizes and/or strips the ADTAG code.

5 Three embodiments of the ADTAG decoder are described. All require an ADTAG decoder which will decode the ADTAG information and accumulate the billing data for downloading to ADTAG. The ADTAG decoders are preferably tamper proof boxes, which are, for example, potted in epoxy, and/or formed with an electronic jumper which automatically erases memory contents when the box is  
10 opened. Each have unique ID's (keys) stored in areas of nonexternally-readable ROM blown into the microprocessor.

The code can be used in three ways:

1) The ADTAG code is broadcast with the commercial. This  
15 has the possible disadvantage noted above that the commercial may be identifiable.

A major advantage of this system is that the ADTAG decoder does not reside at the TV station, but can reside at a remote (secure) ADTAG site 184 that is monitoring the broadcasts of the  
20 TV station. Only those advertisements which are actually broadcast, therefore, are detected.

Certain countermeasures described below could be used to avoid detection of the commercials.

If the code uses a part of the closed captioning, this is  
25 also unlikely to be usable as a means to detect codes, since the

closed captioning occurs on many different types and areas of programs.

2) Alternatively, the ADTAG code is stripped off and detected. The VBI lines used are returned to black before the video is broadcast out.

Here, the ADTAG decoder resides at the TV station, and in series with the live feed. Hence this is a potential degrader of signal quality. It is also subject to "spoofing" by technicians at the station. Hence, one could feed a completely false video stream to the ADTAG box and a completely separate video stream to broadcast.

This could be alleviated by having the ADTAG box monitor the transmission of the TV station by, i.e., including a receiver and matching the claimed live feed to the received live feed. It is difficult, however, to make this system completely secure.

Advantage: nothing is broadcast in the VBI so commercial detection in this way becomes impossible.

3) Another embodiment uses the ADTAG box to add the code to ALL lines including programming, and all lines are broadcast with a code which only ADTAG can decode. Hence if the ADTAG box detects this is an ADTAG coded commercial, it allows the code to pass through after date/time modification. If it detects no ADTAG code it adds a random code to the line. The disadvantage is that the ADTAG box is in series with the live video feed as in b.

above. There are two major advantages: 1) as in the above, the ADTAG monitor can be at a remote site and hence secure. 2) The commercial cannot be distinguished from regular programming.

5        Another possible problem is spoofing by a malicious TV station. That is simply copying the valid ADTAG codes and splicing them onto some other programming, or other commercial tape. They could not read the content of the tape - but copying is easy.

10        But why would the TV station want to do this? This could make it possible to take the ADTAG codes from a 3-minute COKE commercial and splice them onto a 3-minute PEPSI commercial. Thus ADTAG would allow COKE to pay the bill, and the TV station would also collect from PEPSI.

15        According to the present invention, counterfeit prevention techniques are used. A first technique links the actual picture content to the ADTAG code.

20        A technique of characterizing pictures in current programming can be used. For example, one method extracts a quantity such as the average picture brightness level over the last X frames and adds that to the ADTAG code.

For example, this system uses a capacitor or integrator to compute the average brightness level over a line. That analog value is converted to digital and added to the encrypted code.



A sigma-delta ADC could do this all in one operation.

Simple pasting of the code onto a different video would then only work for a video with the same statistics as the original. The actual method does not need to be terribly robust. The A/D need only be at most 3 bits, maybe only 1 bit, e.g., a comparator which compares the average brightness to a threshold. But taken over ALL the lines there is a lot of information. The confidence factor can be changed by increasing the accuracy. Other characteristics could also or alternatively be samples, such as audio, or other more complicated aspects of the picture, including numbers of objects, histogram of colors in the image.

The close captioning embodiment uses identifying information in the existing close captioning lines. Thus, the ADTAG tape would have close caption information, plainly readable, e.g., this is a COKE commercial AD#23456 3 minutes .... END of AD#23456, etc., etc. which would be broadcast out in the clear.

A disadvantage is that anyone can read the info and one can tell the commercial slots. But it has the big advantage that if many people are watching the close caption data, it becomes difficult to change it without detection. If millions of people see a Wally's painting advert on the picture, while COKE is on the close caption data, the phones will ring. Thus, third party verification is possible and spoofing becomes impractical.

Yet another technique uses existing cryptographic techniques to digitally sign the code.

In addition, the ADTAG decoder 141 verifies that the tape was actually broadcast as data is being collected and stripped. Verification of the broadcast is included in the stripped data sent to ADTAG database computer. An alternative to stripping the codes prior to broadcast is to leave the codes on with the broadcast and allow a third party verification of the broadcast with the codes.

When a commercial is aired with associated ADTAG information, the decoder 141 gathers the information from the tape using code stripper 146, and adds to that information a date and time stamp at 148, booking code, ADTAG account code security code and time length of the commercial. Therefore, this information stripped from the ADTAG decoder attached to the live broadcast feed line of the TV station includes:

ADTAG security code (i.e., ADTAG encoded on the master tape)  
TV station code  
Broadcast verification code  
Tape name  
Advertiser code  
Tape production stale date  
Date, time and length of airing

This combined information is sent to the billing computer 162.

The added information is preferably stripped prior to actual broadcast of the live feed as shown in Fig. 1B. This is done to avoid the possibility, as described above, of providing an icon

from which a commercial can be automatically detected. It is important, however, that the information be received while it is actually being transmitted, to ensure real time reception of the advertisement. The central system then matches the following information to its booking system, and provides automatic billing.

If a match is accurate, then the billing system batches the transaction. Later, the system initiates via either modem or Internet:

A banking transaction to remove the reserve from the credit line;

Another banking transmission to add the total amount due to the advertiser;

Another modem transaction to provide advertising agency's cut of this transaction.

An alternative scenario is where there is a problem with the actual airing or with the airing not matching the booking in the system.

All of this functional information will be described in further detail with reference to the remainder of the disclosure.

The basic block diagram of the overall system is shown in Fig. 1B. This block diagram shows the system of stripping the codes at the broadcasting station, shown here as a TV station, prior to transmission. The three major components of the system

include production of the advertisement at 100, airing of the advertisement at 140, and billing of the advertisement at 160 using the ADTAG clearinghouse shown in Fig. 1A.

5       The advertisement is formed by advertising material 102. The advertising material is encoded with special ADTAG information from ADTAG encoder 104. The combined information is placed onto an advertising media 106 which is for example a video tape. The video tape is then used by the television station at 10       140 in order to transmit the information.

15       The transmitted information from TV station 140 is received by an ADTAG receiver 144 which strips the ADTAG code at 146. A real-time clock 148 is combined with the stripped codes to produce a composite stream 150 including both the codes and the real-time information. This information is transferred by a data transfer mechanism 152, for example a modem or some other TCP/IP mechanism.

20       The video information with the code stripped off is transmitted by transmitter 154 in the usual way.

25       The billing information is transferred to billing computer 162 at area 160. The billing computer compares the incoming data with information from its booking database 164. This information is then used for appropriate billing.

      The Fig. 1B block diagram of the system shows the basic functionality of the system. A number of improvements and

modifications are contemplated. Initially, the need for security is paramount in this system. Use of appropriate encryption is crucial for ensuring the security of the system. The encryption must be sufficiently robust to avoid falsification and detect tampering. All of the ADTAG components, including the ADTAG encoder 104, receiver and code stripper 146 and billing computer 162 preferably include encryption and decryption circuitry including the capability of determining any attempt at alteration of the code.

Although this system is described for use with television, it is equally applicable for use with any other communication system, including satellites, closed circuit television, Internet, royalty tracking, radio, or any other means. Also, while the preferred embodiment describes certain identifying information being placed in vertical blanking intervals of the video, and later removed, it should be understood that any form of data encoding which does not interfere with the viewer's watching of the actual commercial could alternately be used. A reverse stripping of the codes, where the codes are broadcasted and stripped by the radio listener and royalty trackers could also be used. Other schemes would include putting the information in the picture itself using steganographic methods. This is currently being done in still images by Digimarc™. These

systems adjust portions of the image that cannot be seen with the naked eye, in a way that encodes the information.

A particularly preferred embodiment described includes  
5 information in the vertical blanking intervals along with the ADTAG codes of a number of different frames. These items of information need to agree and be correct in order to verify the information.

Fig. 1B shows the block diagram for embodiment B where the  
10 ADTAG is stripped off and detected before the video is broadcast. Fig. 1C shows an alternative block diagram for embodiment A where the ADTAG code is received a remote ADTAG site 120 which includes an ADTAG decoder stripping the codes and transferring them to the billing computer system 160.

15 Embodiment C also uses the same block diagram of Fig. 1C.

A diagram of the tape tag encoder system is shown in Fig. 2. The tape tag encoder forms the ADTAG encoder system 104 that is used to tag video material as it is placed on storage media, e.g. tape 106, prior to broadcasting. This system is used for example  
20 at production houses, which produce the advertiser's tapes that are sent to the broadcaster.

Controlling console 200 allows input of certain data to be recorded in the tag. This data includes, for example,  
information about the advertisement including but not limited  
25 video information indicating the advertisement. The video 202

from video source 200 is tagged using a tape tagger element 204.  
The information, once tagged is recorded by a video tape recorder  
206. The tape tagger 204 operates as described with reference to  
5 the schematic of Figs. 5A and 5B to modify the teletext-encoded  
video.

As described above, the preferred mode operates to encode  
the required information into the vertical blanking interval of  
the video signal, e.g., the NTSC signal. Of course, it is also  
10 possible to encode the information into the video signal in other  
ways. The system that is described in the following explains how  
the information is encoded on the video signal.

The schematic of Figs. 5A and 5B shows a schematic which  
carries out the decoding and encoding. The circuit is encased in  
15 potting epoxy for physical security. Also, keys can be held in  
secure areas of RAM that are not externally readable and are only  
readable in the microprocessor internals. The video signal is  
received on the video input port 500. The signal is modified by  
the elements of the circuit. The modified composite video signal  
20 is output through video output port 502. Almost any line can be  
selected, e.g., line 7.

The circuit in Figs. 5A and 5B operates both as an encoder  
and a decoder, based on a software switch. The circuit operates  
as an encoder to replace a line of video in the vertical blanking  
25 interval of an NTSC video signal with a new signal that includes

the desired encoded data. Fig. 5B shows the serial port 550 which is connected to a controlling computer. This controlling computer communicates information, including operating commands which are dated and encoded. Data that has been recovered can be sent to the computer, or sent over the modem line to a central billing computer.

Depending on the amount of data that is transmitted, much of the video signal may be simply passed by the circuit from the video input to the video output. The signal that is unchanged passes through video multiplexer 504 to buffer 506 and is finally output by 502. The portions of the video signal which are altered are treated differently.

The video signal is also sent to video-in node 552 in Fig. 5B. The video-in node 552 is coupled to a PIC microprocessor 554 which carries out the various functions of the circuit. This includes monitoring the timing information from an LM 1881 integrated sync separation chip 556. This circuit indicates occurrences of vertical sync, horizontal sync and burst in the NTSC video. The video processor 556 also indicates whether the video currently represents even or odd field of the NTSC frame for use in selecting which field is encoded.

Processor 554 monitors the sync pulses in order to locate the desired portion of the video blanking interval. Each sync pulse represents the start of a new video frame. Therefore, a



vertical sync event is taken as a reset for the line count. Each horizontal sync pulse indicates the start of another line of video. The program uses these pulses to count lines until reaching the desired line. This desired line, for example line 7, is the portion of the frame which this circuit will encode the user data. This portion is called the VBI window. Almost any line can be selected, e.g., line 7. Some lines are used for sending broadcast level information, and the V-chip uses certain lines. We need to avoid these lines. In fact the ADTAG encoder could look for "the first unused line" and simply use that. It would also change which lines it uses.

The circuit operates according to the flowchart of Fig. 6 to encode information on the video signal. First, processor 554 generates a SampleBlank signal which causes a blank level sampling circuit (blank) to sample the blank level. Processor 554 also sets the program VBI signal to block the original video signal from passing through video multiplexer U8 during this time. During the time that the program/VBI signal is active, the replacement signal passes through video multiplexer U8.

User data is encoded at step 606 in the flow diagram by generating a representation of the user data on the VBI data line. The preferred mode described herein encodes a digital "0" as the equivalent of a white dot in the video signal and encodes a 0 as a black dot. It is also possible to encode the

information in analog form by changing the color levels for  
example. Processor 554 interfaces to the serial port via serial  
port driver 560 using a slave microprocessor 562 to carry out  
5 appropriate formatting of information including control commands  
and user data. Serial port driver adjust the signal level from  
the PIC level used by the PIC microprocessor to a RS 232  
communication level. The slave processor 562 can be for example  
a PCI processor which generates the sequences required to drive  
10 the display and interface to the ports.

The SampleBlank signal described above is fed to at least  
two circuits. SampleBlank is fed to transistor 510 along with  
the associated circuit 512 including an operational amplifier.  
When SampleBlank is asserted, the transistor 510 conducts causing  
15 capacitor 514 to charge and discharge in equilibrium with the  
input video signal. When SampleBlank is later deasserted, C2  
sees high impedances on the output of transistor and the input of  
operational amplifier 512.

Blank reference signal is formed by op amp 512 which buffers  
20 this signal to a DC voltage to generate the blank reference  
signal 514 which operates as a reference for the blank. The  
blank reference signal is combined with the VBI insert signal  
which has been elsewhere produced and is buffered by op amp  
circuit 516 and 518. The combined signal at node 520 is further  
25 buffered by circuits 522 and 524. These circuits are well known

softening circuits which decrease the slopes of the voltage swings in order to avoid false color information.

SampleBlank also feeds transistor 530 and its circuit. The SampleBlank turns on transistor 530 causing it to conduct and thereby bringing the clamped video signal 532 to its low potential. When SampleBlank is deasserted, transistor 530 is commanded to its high impedance state allowing the clamped video signal 532 to track the relative voltage swings of the video signal. For example, therefore, when the clamped video signal is near 0 volts, the output video signal is black representing a zero bit in the user data. At some threshold above zero volts, say two volts, the video signal is encoded as white, representing a digital "1" in the user data.

Circuit 534 forms a threshold detection circuit which compares the input signal 532 with a variable threshold which can be adjusted by potentiometer 536. The output of the potentiometer forms the VBI detect 538 which is used by processor 554.

The above has described the encoding operation. Much of this operation is common for the decoding.

The receiver 144 and code stripper 146 are located at the video transmitting site, to allow the ADTAG information to be stripped off prior to transmission. Data transfer 152 is also affected by the circuit of Figs. 5A/5B. In view of the

similarities of operation, the same circuit of Figs. 5A/5B is used to decode the information. This allows certain economies and saves on the cost of hardware. The circuit operates as either a decoder or an encoder based on a selection by a switch, a software switch, or an automatic detection of ADTAG information, for example.

Fig. 7 shows a block diagram of the operation. The information is received by video receiver 154. Monitor 700 includes the structure which strips codes and transfers data. The data is recorded by recorder 702 and also sent by modem 152 to the billing computer 162. The controlling console 704 enables certain systems to be appropriately controlled.

As described above, the same system is used, but in this case controlled according to the flow diagram of Fig. 8.

The flow diagram begins at step 800 by determining the beginning of a video frame. Using a similar operation to that discussed above with respect to the encoding, the indication of vertical sync that is produced by processor 554 on its line 7 is used to indicate the beginning of the video frame at step 800. After that, video lines are counted at step 802 by counting each sync pulse. When the desired line is reached, this indicates the beginning of the VBI window. This line is then selected as a dummy at step 804 in order to remove the data from that signal.

As described above, white dots are reconstructed as zeros and

black dots are reconstructed as ones. This reconstruction is  
synchronized with a clock at step 806 in order to remove the  
data. The data is read at step 808 followed by switching back to  
5 the incoming video at step 810 to pass the rest of the frame  
unaltered.

10 The data thereby stripped off at step 812 is sent via  
secured communications e.g. by encrypted modem information to the  
billing computer 162. The ADTAG database computer takes the  
information received in Chart 2 ("Stripped Information") and  
matches it to the information entered in Chart 1 ("Booking -  
Information"). If items 1-4 of the booking information match,  
then items 5-6 are approved and set up for payment. Items 1-4  
are time, date, duration, TV station, Advertiser and tape  
15 information. Items 5 and 6 are price and ad agency. Payment is  
then processed by ADTAG by electronic transfer between the banks  
of the TV station, Ad agency and Advertiser.

The most common errors that occurred are:

- 20
- Commercial didn't air for the correct length of time (i.e. last 5 seconds were cut off).
  - Commercial didn't air on the proper date and time.
  - Stale tape was used.

25 These errors and additional errors that arise will be  
processed in a manner pre-established with all parties involved.  
Payment will be delayed until error is resolved according to  
these procedures. Some errors may fall in parameters that all

entities have approved as acceptable and payment will not be delayed.

For instance a 4 second cut-off may be acceptable and will be paid perhaps accordingly discounted. A 15-second cut-off is not acceptable and will be charged back to the TV station. All error processing will be listed out in contracts signed by all members of the ADTAG clearinghouse.

In addition, errors where no airings occurred, but the booking remains in the ADTAG system will also be resolved on a basis to be established prior to entry to the ADTAG clearinghouse system. Therefore if a booking remains after the air date has passed the advertiser still has a reserve on its credit line that needs to be resolved and reversed.

#### Security

An important part of the ADTAG system is the use of security to avoid the possibility of fraud. Without security, the system could be fraudulently manipulated.

As shown above, the teletext system provides a basic physical layer protocol for the data transmission. The transport and link layers must be specified in order to encode the data to ensure reliability and privacy. The system uses layering of error detection and correction mechanisms. For example the frames of data are encoded to guard against bad data at the

receiver. The data can also be encrypted in block cipher mode using a periodically changing session key and public keying encryption algorithm. The details are shown in Fig. 4.

5           Fig. 9 shows a flow chart of operation which corresponds to the verification and authorization described above. Step 900 corresponds to the detecting of identification information within the commercial. As described above, this can correspond to obtaining information in a number of different ways, from a number of different places including but not limited to the vertical blanking interval and the closed captioning locations. Step 902 corresponds to a verification. This verification step can be carried out by operating in a secure premises. In those embodiments that do use a secure premises, the premises itself corresponds to the verification. Verification may include detecting the security of the encryption, correlating the commercial content, or comparing encryption in the vertical blanking with encryption in the closed captioning, for example. If verification is positive, a time and day stamp is added at step 904. This corresponds to a real time indication of when the commercial was actually broadcast.

Step 906 begins the determination of whether the commercial was broadcast when it was supposed to. First, the commercial identification is compared against the database.

At step 908, an indication of whether the identification matches the time and day when a schedule is determined. If so, the bank is authorized to pay the fee for the commercial, since everything was properly done as scheduled.

If not, an error resolution system is determined at step 912. For each client, a separate error resolution system may be in place, or alternatively there could be a number of different error resolution systems which are applicable to different clients. The simplest error resolution system is that the commercial simply did not play. A more difficult scenario is when the commercial did play, but played at the wrong time. A system can, for example, say that when the time differed by a certain amount, that the bill would be reduced by 50%. Other rules which are beyond the scope of this patent application could also be used.

At step 914, the system determines that error resolution is not available, and kicks out the system for manual resolution at that point.

Other modifications are within the disclosed embodiment. For example, other media including radio, cable, and others are contemplated.



What is claimed is:

1. A method of scheduling and paying for comprising:  
booking a advertising segment with an advertising agency, said booking comprising determining time, network, pricing and commission parameters for said advertising segment;

establishing an account with a clearinghouse, said clearinghouse determining if the commercial actually aired at the specified time by automatically detecting a code on the commercial and verifying security of said code; and

said clearinghouse automatically authorizing payment if said commercial played at the specified time and automatically authorizing an error resolution procedure if the commercial played at other than the specified time.

2. A method as in claim 1, wherein said error resolution determines if the commercial has played within a specified interval of the specified time and allowing payment if so.

3. A method as in claim 1, wherein said security comprises information on the advertisement correlated with the advertisement.

09:24:09 "031200"

**Abstract**

Advertising is marked with a code in a way which makes it difficult to fool the system. The advertising is marked with a code at the time the advertising is produced. Then, when the advertising is broadcast, the code on the advertising is analyzed. Different security measures can be used, including producing the code in the closed captioning so that many different people can see the code, or comparing codes in one part of the signal with a code in another part of the signal. Measures are taken to prevent the code from being used to detect commercials. According to another part of this system, a paradigm for a clearinghouse is disclosed in which the user signs up with the clearinghouse, obtains a line of credit, and the advertiser, the agency, and the ad producer also subscribe to the service. When the ad is actually aired, the payment can be automatically transferred.

093343-0100





FIG 1A

Parameter	Value	Standard Error	z	P
Intercept	1.000	0.000		
Age	0.000	0.000	0.00	1.00
Age <sup>2</sup>	0.000	0.000	0.00	1.00
Age <sup>3</sup>	0.000	0.000	0.00	1.00
Age <sup>4</sup>	0.000	0.000	0.00	1.00
Age <sup>5</sup>	0.000	0.000	0.00	1.00
Age <sup>6</sup>	0.000	0.000	0.00	1.00
Age <sup>7</sup>	0.000	0.000	0.00	1.00
Age <sup>8</sup>	0.000	0.000	0.00	1.00
Age <sup>9</sup>	0.000	0.000	0.00	1.00
Age <sup>10</sup>	0.000	0.000	0.00	1.00
Age <sup>11</sup>	0.000	0.000	0.00	1.00
Age <sup>12</sup>	0.000	0.000	0.00	1.00
Age <sup>13</sup>	0.000	0.000	0.00	1.00
Age <sup>14</sup>	0.000	0.000	0.00	1.00
Age <sup>15</sup>	0.000	0.000	0.00	1.00
Age <sup>16</sup>	0.000	0.000	0.00	1.00
Age <sup>17</sup>	0.000	0.000	0.00	1.00
Age <sup>18</sup>	0.000	0.000	0.00	1.00
Age <sup>19</sup>	0.000	0.000	0.00	1.00
Age <sup>20</sup>	0.000	0.000	0.00	1.00
Age <sup>21</sup>	0.000	0.000	0.00	1.00
Age <sup>22</sup>	0.000	0.000	0.00	1.00
Age <sup>23</sup>	0.000	0.000	0.00	1.00
Age <sup>24</sup>	0.000	0.000	0.00	1.00
Age <sup>25</sup>	0.000	0.000	0.00	1.00
Age <sup>26</sup>	0.000	0.000	0.00	1.00
Age <sup>27</sup>	0.000	0.000	0.00	1.00
Age <sup>28</sup>	0.000	0.000	0.00	1.00
Age <sup>29</sup>	0.000	0.000	0.00	1.00
Age <sup>30</sup>	0.000	0.000	0.00	1.00
Age <sup>31</sup>	0.000	0.000	0.00	1.00
Age <sup>32</sup>	0.000	0.000	0.00	1.00
Age <sup>33</sup>	0.000	0.000	0.00	1.00
Age <sup>34</sup>	0.000	0.000	0.00	1.00
Age <sup>35</sup>	0.000	0.000	0.00	1.00
Age <sup>36</sup>	0.000	0.000	0.00	1.00
Age <sup>37</sup>	0.000	0.000	0.00	1.00
Age <sup>38</sup>	0.000	0.000	0.00	1.00
Age <sup>39</sup>	0.000	0.000	0.00	1.00
Age <sup>40</sup>	0.000	0.000	0.00	1.00
Age <sup>41</sup>	0.000	0.000	0.00	1.00
Age <sup>42</sup>	0.000	0.000	0.00	1.00
Age <sup>43</sup>	0.000	0.000	0.00	1.00
Age <sup>44</sup>	0.000	0.000	0.00	1.00
Age <sup>45</sup>	0.000	0.000	0.00	1.00
Age <sup>46</sup>	0.000	0.000	0.00	1.00
Age <sup>47</sup>	0.000	0.000	0.00	1.00
Age <sup>48</sup>	0.000	0.000	0.00	1.00
Age <sup>49</sup>	0.000	0.000	0.00	1.00
Age <sup>50</sup>	0.000	0.000	0.00	1.00
Age <sup>51</sup>	0.000	0.000	0.00	1.00
Age <sup>52</sup>	0.000	0.000	0.00	1.00
Age <sup>53</sup>	0.000	0.000	0.00	1.00
Age <sup>54</sup>	0.000	0.000	0.00	1.00
Age <sup>55</sup>	0.000	0.000	0.00	1.00
Age <sup>56</sup>	0.000	0.000	0.00	1.00
Age <sup>57</sup>	0.000	0.000	0.00	1.00
Age <sup>58</sup>	0.000	0.000	0.00	1.00
Age <sup>59</sup>	0.000	0.000	0.00	1.00
Age <sup>60</sup>	0.000	0.000	0.00	1.00
Age <sup>61</sup>	0.000	0.000	0.00	1.00
Age <sup>62</sup>	0.000	0.000	0.00	1.00
Age <sup>63</sup>	0.000	0.000	0.00	1.00
Age <sup>64</sup>	0.000	0.000		

100



1161B

004760" 62432560




FIG 1C

Variable	Mean	SD	Min	Max
Age	34.5	10.2	22	55
Gender	0.5	0.5	0	1
Marital status	0.6	0.5	0	1
Education	12.5	1.5	10	15
Income	1500	500	1000	2500
Health status	0.8	0.2	0	1
Smoking status	0.3	0.5	0	1
Alcohol consumption	0.2	0.4	0	1
Exercise frequency	0.5	0.5	0	1
Stress level	0.7	0.3	0	1
Sleep quality	0.6	0.4	0	1
Work satisfaction	0.5	0.5	0	1
Life satisfaction	0.7	0.3	0	1
Depression score	10.5	5.0	0	30
Anxiety score	12.0	6.0	0	30
Quality of life score	75.0	10.0	60	90




FIG 2

~~Figure 1. AdvoTech Tape Tagging System~~

—



3




Figure 4. Transport/Data Link Encoding

4



500











FIG 5A

Title		Author
VBI Frequency Modulator		...
Values selection, calculation and VBI data de section 5.1.2		...
Size	...	...
Date	10 Apr 1986	...
Doc	HA-BRON-BI-UN-01-01	...
Sheet	...	...
Drawn by	...	...

Video



F16 SB



Title	Video Input Decoder
Author	Jim Decker
Size	B
Date	26 Apr 1986
File	16V-BIO-21-BIO-01.M

# Encoder Flow Diagram




FIG 6

004760-6482560

0933479-031700





Table 1. Demographic characteristics of the study population	
Age (years)	65.0 ± 10.0
Gender	
Male	50 (50.0%)
Female	50 (50.0%)
Education (years)	12.0 ± 2.0
Marital status	
Married	40 (80.0%)
Single	10 (20.0%)
Occupation	
Retired	30 (60.0%)
Unemployed	20 (40.0%)
Income (USD/month)	1000.0 ± 500.0
Health status	
Good	30 (60.0%)
Poor	20 (40.0%)
Comorbidities	
Hypertension	15 (30.0%)
Diabetes	10 (20.0%)
Cholesterol	12 (24.0%)
Arthritis	8 (16.0%)
Other	5 (10.0%)



0958479-031700




FIG 9

## COMBINED DECLARATION AND POWER OF ATTORNEY

As a below named inventor, I hereby declare that:

My residence, post office address and citizenship are as stated below next to my name,

I believe I am the original, first and joint inventor of the subject matter which is claimed and for which a patent is sought on the invention entitled

## TELEVISION ADVERTISING AUTOMATED BILLING SYSTEM

the specification of which

☐ is attached hereto.

☒ was filed on 11/26/97 as Application Serial No. 08/979,838 and was amended on .

☐ was described and claimed in PCT International Application No. \_\_\_\_\_  
filed on \_\_\_\_\_ and as amended under PCT Article 19 on \_\_\_\_\_.

I hereby state that I have reviewed and understand the contents of the above-identified specification, including the claims, as amended by any amendment referred to above.

I acknowledge the duty to disclose all information I know to be material to patentability in accordance with Title 37, Code of Federal Regulations, §1.56.

I hereby claim the benefit under Title 35, United States Code, §120 of any United States application(s) listed below and, insofar as the subject matter of each of the claims of this application is not disclosed in the prior United States application in the manner provided by the first paragraph of Title 35, United States Code, §112, I acknowledge the duty to disclose all information I know to be material to patentability as defined in Title 37, Code of Federal Regulations, §1.56(a) which became available between the filing date of the prior application and the national or PCT international filing date of this application:

U.S. SERIAL NO.	FILING DATE	STATUS
_____	_____	<input type="checkbox"/> Pending <input type="checkbox"/> Issued <input type="checkbox"/> Abandoned

I hereby appoint the following attorneys and/or agents to prosecute this application and to transact all business in the Patent and Trademark Office connected therewith: Scott C. Harris, Reg. No. 32,030; William J. Egan, III, Reg. No. 28,411; David L. Feigenbaum, Reg. No. 30,378; John F. Land, Reg. No. 29,554; Ralph A. Mittelberger, Reg. No. 33,195; Hans R. Troesch, Reg. No. 36,950 and John R. Wetherell, Jr., Reg. No. 31,678 of Fish & Richardson P.C.

Address all telephone calls to Scott C. Harris at telephone number 619/678-5070.

Address all correspondence to Scott C. Harris, Fish & Richardson P.C., 4225 Executive Square, Suite 1400, La Jolla, CA 92037.

I hereby declare that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge

## COMBINED DECLARATION AND POWER OF ATTORNEY CONTINUED

that willful false statements and the like so made are punishable by fine or imprisonment, or both, under Section 1001 of Title 18 of the United States Code and that such willful false statements may jeopardize the validity of the application or any patents issued thereon.

Full Name of Inventor: RODNEY M. GOODMAN

Inventor's Signature: [Signature]

Date: 6-8-98

Residence Address: 462 E. LAS FLORES DRIVE, ALTADENA, CA 91001

Citizen of: U.K.

Post Office Address: \_\_\_\_\_

Full Name of Inventor: KAREN EMERSON

Inventor's Signature: \_\_\_\_\_

Date: \_\_\_\_\_

Residence Address: \_\_\_\_\_

Citizen of: \_\_\_\_\_

Post Office Address: \_\_\_\_\_

JEFFREY

Full Name of Inventor: JEFFERY DICKSON

Inventor's Signature: [Signature]

Date: 5/20/98

Residence Address: 1155 E. DELMAR BLVD #207, PASADENA CA 91106

Citizen of: CANADA

Post Office Address: 26 CAMEO CRES, WINNIPEG MB CANADA R2K 2W4

IF CANADIAN  
ADDRESS REQUIRED



## COMBINED DECLARATION AND POWER OF ATTORNEY CONTINUED

that willful false statements and the like so made are punishable by fine or imprisonment, or both, under Section 1001 of Title 18 of the United States Code and that such willful false statements may jeopardize the validity of the application or any patents issued thereon.

Full Name of Inventor: RODNEY M. GOODMAN

Inventor's Signature: \_\_\_\_\_ Date: \_\_\_\_\_

Residence Address: \_\_\_\_\_

Citizen of: \_\_\_\_\_

Post Office Address: \_\_\_\_\_

Full Name of Inventor: KAREN EMERSON

Inventor's Signature: Karen Emerson Date: 6-9-98

Residence Address: 618 Downtown Marina 450 Shoreline Dr.

Citizen of: U.S.A. Long Beach Ca 90802

\* Post Office Address: PO Box 1062 Long Beach Ca. 90801  
Mailing

Full Name of Inventor: JEFFERY DICKSON

Inventor's Signature: Jeffery Dickson Date: 5/20/98

Residence Address: \_\_\_\_\_

Citizen of: CANADA

Post Office Address: \_\_\_\_\_

47975.111

0052849-03100